PLANT 2 · QUALITY PROCEDURE

First-Off Approval

QP-306
Rev C

Effective	Owner	Prepared by	Approved by
2024-05-20	**Quality**	**P. Nakamura**	**H. Costa**

PURPOSE

Confirm the first product after a start-up or changeover is right before the line runs at rate.

SCOPE

Every start-up, product changeover and size changeover on Lines 1, 2 and 3.

ROLES

ROLE	RESPONSIBILITY
QA Technician	Carries out the checks and signs.
Operator	Supplies the samples.
Line Lead	Holds the line until approval.

PPE

- Safety glasses
- Safety shoes

TOOLS

- Check scale (0.1 g)
- Torque tester
- Approved label artwork binder

MATERIALS

None.

PROCEDURE

Checks

STEP	WHO	ACTION
1	Operator	Bring the first 5 good bottles and one packed case to the QA bench.
2	QA Technician	Fill weight: all 5 bottles inside the limits in WI-210.
3	QA Technician	Cap: correct cap, removal torque inside the range in WI-211.
4	QA Technician	Label: correct artwork against the binder, straight within 2 mm, no wrinkles or bubbles.

5	QA Technician	Lot code: readable, correct format (see QP-316), correct date and shift.
6	QA Technician	Case: correct count, case label matches the product, glue seal good.

Decision

STEP	WHO	ACTION
7	QA Technician	All checks pass: sign FRM-QA-06 First-Off Record and tell the Line Lead.
8	QA Technician	Any check fails: the line stays stopped. The Line Lead corrects the fault and a new first-off is taken.
9	Line Lead	Do not run above 50% speed before approval.

RELATED DOCUMENTS

- QP-303 Fill Weight Checks
- WI-211 Capper Setup and Torque Check
- QP-316 Customer Complaints and Lot Trace

RECORDS

- FRM-QA-06 First-Off Record

REVISION HISTORY

REV	DATE	CHANGE
C	2024-05-20	Lot code check added.
B	2022-01-10	Case check added.